BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

Schedule - B

BBMP/2021-22/OW/WORK_INDENT50600

Name of Work: Maintenance & Repairs of Footpath and Roads in ward No 14, Bagalagunte

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri B K NAGENDRA	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. specification.	Cum	123.20	269.3	Rupees Two Hundred Sixty Nine and Thirty Paise Only
2	Providing and laying in position plain cement concrete of mix1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregtes @ 0.57 cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	18.48	4595.27	Rupees Four Thousand Five Hundred Ninety Five and Twenty Seven Paise Only
3	:Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications.	Sqm	268.80	680.01	Rupees Six Hundred Eighty and One Paise Only

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division.

4	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.460 cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6	Cum	77.28	5096.95	Rupees Five Thousand Ninety Six and Ninety Five Paise Only
5	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (TMT bars FC 500)	Tonne	4.64	78734.94	Rupees Seventy Eight Thousand Seven Hundred Thirty Four and Ninety Four Paise Only
6	Providing and and fixing Precast Concrete slab 100 MM thick witth all lead and lift as per specification	Sqm	201.60	1985.74	Rupees One Thousand Nine Hundred Eighty Five and Seventy Four Paise Only
7	Transportaion & disposing of the excavated earth obtained from side drains & high burns an either sides of the road 2km lead	Cum	123.20	72.26	Rupees Seventy Two and Twenty Six Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Executive Engineer,
Dasarahalli Division